



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Moody of Leben Oil Corp. has this

date requested permission to plug the following described well:

Mr. Moody guarantees payment of the plugging fee.

Operator's full Name: Leben Oil Corporation

Complete Address: Box 486, Great Bend, Kansas

Lease Name: Doll Well No. 1

Location: C SW Sec. 18 Twp. 34 Rge. 31 (O) (W)

County: Seward Total Depth 6403' Oil Well X

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Moody was instructed to plug the well as follows:

8 5/8" to 1500' circulated w/ cement. 5 1/2" to 6403' cemented.


Top perforations 4402' Plug bottom w/ 35 sacks cement

Top of cement 3211' Mud 3211' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent