



JOHN CARLIN
R. G. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

14 April 1982

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-175-20618

Dear Sir:

Mr. Dale Stromquist of Quingue Oil & Gas Production has this date requested permission to plug the following described well:

Operator's Full Name: Quingue Oil & Gas Production

Complete Address: 18 West 3rd St. Liberal Kansas 67901

Lease Name: Be good Well No. 1-20

Location: C-SE-NW Sec. 20 Twp. 34 Rge. 31 (E) (W)

County: Seward Total Depth: 6500'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Stromquist was instructed to plug the well as follows:

They set 1503' of 8 5/8" surface casing cement articulated the anhydrite was at 1485'. 1st plug at 1530' with 70 sby of cement. 2nd plug at 750' with 25 sby of cement. 3rd plug on solid bridge at 40' to 0' with 10 sby of cement. They circulated 10 sby of cement in rat hole & 5 sby of cement in mouse hole. The cement was pumped through drill pipe. The plugging was accomplished by Halliburton Co.

Very truly yours,

Paul A. Luthi
Conservation Division Agent