

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Carter of Venus has this

date requested permission to plug the following described well:

Mr. Carter guarantees payment of the plugging fee.

Operator's full Name: Venus Oil Company

Complete Address: 1200 Nat'l Bk of Commerce Bldg., San Antonio, Texas

Lease Name: Shafer Heirs Well No. 1

Location: NW SE Sec. 2 Twp. 34 Rge. 31 XX (E) (W)

County: Seward Total Depth 6070' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Carter was instructed to plug the well as follows:

10 3/4" to 1349' circulated w/ cement. 7" to 5228' cemented.

Top perforations 5119' Plug bottom w/ 25 sacks cement.

Top of cement 5020' Mud 5202' to 800'

Spot 40 sacks cement 800' to 700' Mud 700' to 35'

Plug, Hulls & 15 sacks cement 35' to 0'.

Very truly yours,


Conservation Division Agent