

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wood of Texaco has this

date requested permission to plug the following described well:

Mr. Wood guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: Box 2420, Tulsa, Oklahoma 74102

Lease Name: A & H Adams Well No. 2

Location: SE SE Sec. 36 Twp. 34 Rge. 30 (E) (W)

County: Meade Total Depth 6430' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wood was instructed to plug the well as follows:

13 3/8" to 413' circulated w/ cement. 9 5/8" to 2864' circulated w/ cement.

7" liner 2651' to 6400' cemented. Top perforations 5874'

Plug bottom w/ 30 sacks cement. Top of cement 5770'

Mud 5770' to 2880' Spotted 90 sacks cement 2880' to 2330'

Mud 2330' to 450' Spotted 60 sacks cement 450' to 300'

Mud 300' to 40' Plug, hulls & 15 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent