

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1974

CONSERVATION DIVISION  
(Wichita, Kansas)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Luck of Thomas has this

date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas Petroleum

Complete Address: Box 1177, Liberal, Kansas

Lease Name: Fox Well No. 3

Location: NE NE SW Sec. 35 Twp. 34 Rge. 30 XX (E)(W)

County: Meade Total Depth 6052' Oil Well         

Gas Well X Input Well          SWD Well          D & A          Lost Hole         

Mr. Luck was instructed to plug the well as follows:

8 5/8" to 1445' circulated w/ cement. 5 1/2" to 6024' cemented.


Top perforations 5900' Plug bottom w/ 20 sacks cement.

Top of cement 5740' Mud 5740' to 900'

Spot 30 sacks cement 900' to 800' Mud 800' to 40'

Plug, Halls & 10 sacks cement 45' to 00.

Very truly yours,

  
Conservation Division Agent