

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1968

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pulley of S&S Pipe & Supply has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: S&S Pipe & Supply Company

Complete Address: 1209 Mid-Continent Bldg., Tulsa, Oklahoma

Lease Name: Fox Well No. 1

Location: C SE SW Sec. 34 Twp. 34 Rge. 30 (E) (W)

County Meade Total Depth 6140' Oil Well X

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

8 5/8" to 2603' circulated w/ cement. 5 1/2" to 5975' cemented.

Top perforations 5918' Plug bottom w/ 20 sacks cement &

Top of cement 5800' Mud 5800' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edna J. Eves  
Conservation Division Agent