

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Red Clark has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Red Clark Inc.

Complete Address: Box 638, Spearman, Texas 79081

Lease Name: Rimrock Well No. 1

Location: C SW NE Sec. 32 Twp. 34 Rge. 30 XX (E) (W)

County: Meade Total Depth 5900' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1362' circulated w/ cement. 4 1/2" to 4568' cemented.

Top perforations 4491' Plug bottom w/ 20 sacks cement.

Top of cement 4390' Mud 4390' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar A. Lucas
Conservation Division Agent