

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-26604-00-00  
Spot: SENWNE Sec/Twnshp/Rge: 28-27S-18E  
488 feet from N Section Line, 965 feet from E Section Line  
Lease Name: BEACHNER BROS Well #: 28-27-18-2  
County: NEOSHO Total Vertical Depth: 1062 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1058		125 SX
SURF	8.625	31		30 SX
T1	2.375	701		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/05/2015 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: KEN PAULIE Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 02/06/2015 8:00 AM KCC Agent: ALAN DUNNING

**Actual Plugging Report:**

A 2.375 inch cement string was lowered to 1050 ft. The well was then pumped full of cement from btm to top thru the cement string. The cement string was pulled and the well topped off with cement. The well was cut off below plow depth and the location restored. A total of 103 sacks of portland cement were used to plug well.

**Perfs:**

Top	Bot	Thru	Comments
650	652		
616	619		
598	600		
522	526		
513	517		

RECEIVED  
KCC DIST # 3  
MAR 30 2015  
CHANUTE, KS

AD

Remarks:

Plugged through: TBG

4/8/15 *ckm*

District: 03

Signed Alan M. Dunning  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 02 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3