

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-26672-00-00  
Spot: NWENW Sec/Twnshp/Rge: 22-27S-18E  
630 feet from N Section Line, 1850 feet from W Section Line  
Lease Name: BEACHNER BROS 'A' Well #: 22-27-18-3  
County: NEOSHO Total Vertical Depth: 1010 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1001		100 SX
SURF	8.625	45		34 SX
T1	2.375	823		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/06/2015 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: KEN PAULIE Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF WITH CEMENT.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 02/06/2015 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was lowered to 1000 ft. The well was then pumped full of cement from btm to top thru the cement string. The cement string was pulled and the well topped off with cement. A total of 116 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
797	799		
653	656		
648	650		
520	524		
510	514		

RECEIVED  
KCC DIST # 3  
MAR 30 2015  
CHANUTE, KS

AD

Remarks:

Plugged through: TBG

4/8/15 ckm

District: 03

Signed Alan Dunning  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 02 2015  
CONSERVATION DIVISION  
WICHITA, KS