

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21742-00-00
Spot: W2E2SESW Sec/Twnshp/Rge: 3-35S-5W
660 feet from S Section Line, 2020 feet from W Section Line
Lease Name: KOLARIK Well #: 3-1
County: HARPER Total Vertical Depth: 5300 feet

Operator License No.: 31253
Op Name: PRIMEXX OPERATING CORPORATION
Address: 4849 GREENVILLE # 1600
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7.875	5293	2600	225 SX
SURF	8.625	226		300 SX
T1	2.875	5023		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2015 8:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: JONATHAN Company: JERRY DUNKIN, INC. Phone: _____

Proposed Plugging Method: CIBP @ 4490'. REC 2600'. 35 SXS @ 1000', 35 SXS @ 700'. CIRCULATE 280'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2015 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4490' CAPPED WITH 3 SXS CEMENT. RAN TUBING TO BOTTOM & FILLED CASING WITH MUD. REC CASING FROM 2600' & PULLED FROM WELLBORE. RAN TUBING TO 1000', SPOTTED 35 SXS CEMENT. PULLED TUBING TO 700' & SPOTTED 35 SXS CEMENT. PULLED TUBING TO 280' & CIRCULATE CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5044	5072	CSG	
504	5072	CSG	

Remarks: JERRY DUNKIN CEMENT & PLUGGING

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

4/8/15 CKM

Received
KANSAS CORPORATION COMMISSION

APR 03 2015

CONSERVATION DIVISION
WICHITA, KS

JK