

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20203-00-02
Spot: NWSE Sec/Twnshp/Rge: 2-17S-29W
1938 feet from S Section Line, 1937 feet from E Section Line
Lease Name: GILL Well #: 1
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 30029
Op Name: STANDARD OPERATING COMPANY
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		
CIBP		3995		
CIBP		4480		
DVT	4.5	2100		WITH 500 SX CMT
PROD	4.5	4617	0	WITH 250 SX CMT
SURF	8.625	280		WITH 185 SX CMT

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 03/13/2015 11:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: DAVID PAULY Company: STANDARD OPERATING Phone: (785) 798-5051

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS. RUN TBG TO 1800' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2015 12:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 1720' WITH 5 SX CMT. RUN TBG TO 1650' & PUMPED 130 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 100#.

Perfs:

Top	Bot	Thru	Comments
4545	4548		
4538	4542		
4515	4518		
4508	4513		
4392	4396		
4378	4382		
1850	1880		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

APR 02 2015

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
MAR 24 2015

KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)