

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20257-00-00  
Spot: N2SWNE Sec/Twnshp/Rge: 2-17S-29W  
3613 feet from S Section Line, 1963 feet from E Section Line  
Lease Name: GILL A Well #: 2  
County: LANE Total Vertical Depth: 4585 feet

Operator License No.: 30029  
Op Name: STANDARD OPERATING COMPANY  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	2190		WITH 500 SX CMT
PROD	5.5	4579	0	WITH 200 SX CMT
SURF	8.625	264		WITH 170 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2015 8:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID PAULY Company: STANDARD OPERATING Phone: (785) 798-5051

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS. RUN TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/13/2015 9:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4000' WITH 5 SX CMT. RUN TBG TO 2200' & PUMPED 235 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 100#.

Perfs:

Top	Bot	Thru	Comments
4516	4519		
4509	4513		
4328	4334		
4312	4317		
4158	4168		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

4/8/15 CKM

District: 01

Signed Michael J. Maier  
SA (TECHNICIAN)

RECEIVED  
MAR 24 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

APR 02 2015

CONSERVATION DIVISION  
WICHITA, KS