

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20247-00-01  
Spot: SWNWNW Sec/Twnshp/Rge: 1-17S-29W  
4179 feet from S Section Line, 4938 feet from E Section Line  
Lease Name: JAMES C Well #: 1  
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 30029  
Op Name: STANDARD OPERATING COMPANY  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4619	0	WITH 75 SX CMT
SURF	8.625	323		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/06/2015 11:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE PAULEY Company: STANDARD OPERATING Phone: (785) 798-5051

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS. PERFORATE AT 1250' & PUMP 80 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/06/2015 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4480' WITH 5 SX CMT. TIED ONTO CASING & PUMPED 200 SX CMT. MAXIMUM PRESSURE 900#. SHUT IN PRESSURE 250#. TIED ONTO BACKSIDE & PUMPED 150 SX CMT. WELL WAS ON VACUUM WHEN DONE. 3/13/15: TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4550	4552		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

4/8/15 CKM

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAR 24 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION Form CP-2/3  
APR 02 2015  
CONSERVATION DIVISION  
WICHITA, KS