

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-20305-00-01  
Spot: SWNWSE Sec/Twnshp/Rge: 17-11S-16W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ALBRECHT Well #: 1  
County: ELLIS Total Vertical Depth: 3300 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5030</u>	<u>PROD</u>	<u>5.5</u>	<u>3325</u>		<u>125 SX</u>
Op Name: <u>VESS OIL CORPORATION</u>	<u>SURF</u>	<u>8.625</u>	<u>965</u>		<u>500 SX</u>
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2015 9:00 AM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP Phone: (785) 885-8240

Proposed Plugging Method: Ordered 590 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2015 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 940'. Ran tubing to 3000' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1426' and pumped 110 sx cement w/300 # hulls. Cement circulated out the backside. POOH. Filled casing with 27 sx cement. Hooked to braden head and pumped 23 sx cement at 200 psi. Circulated cement out of the casing. Shut in.  
GPS: 39.09344 -099.12019

Perfs:

Top	Bot	Thru	Comments
3054	3057		

Remarks: BASIC ENERGY SERVICES TICKET # 12065

Plugged through: TBG

4/8/15 CKM

District: 04

Signed Ray AD in KED

(TECHNICIAN)

CM

MAR 19 2015

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 06 2015

CONSERVATION DIVISION  
WICHITA, KS