

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-01644-00-00
Spot: S2N2SWSW Sec/Twnshp/Rge: 34-9S-25W
760 feet from S Section Line, 4620 feet from E Section Line
Lease Name: ROME ESTATE Well #: 4
County: GRAHAM Total Vertical Depth: 4023 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4013		100 SX
SURF	8.625	328		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2015 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: SMOKEY HILL WELL Phone: (785) 885-8240

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement and 500 # hulls.
Shot perforations at 2250', 2175', 1329' and 320'.
Perforations at 3797' - 3801', 3815' and 4015'.
Junk in hole at 3723'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2015 3:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3687' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3348' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2449' and pumped 200 sx cement w/300 # hulls. Good circulation of cement. Pulled tubing out. Casing standing full. Tied on to backside and pumped 65 sx cement. Shut in pressure 50 psi.

GPS: 39.22100 -100.10546

Perfs:

Top	Bot	Thru	Comments
3815	4015		
3797	3801		

Remarks: BASIC CEMENT TICKET # 112066

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN) CM

4/8/15 CCM

MAR 19 2015

Received
KANSAS CORPORATION COMMISSION

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3