

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20724-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 8-12S-15W
990 feet from N Section Line, 1650 feet from E Section Line
Lease Name: OSWALD WILCOX A Well #: 24
County: RUSSELL Total Vertical Depth: 3221 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5030</u>	<u>PROD</u>	<u>4.5</u>	<u>3215</u>		<u>450 SX</u>
Op Name: <u>VESS OIL CORPORATION</u>	<u>SURF</u>	<u>8.625</u>	<u>134</u>		<u>125 SX</u>
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2015 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP Phone: (785) 885-8240

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Casing leak at 2358' - 2360'. DV Tool at 859' w/225 sx cement

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2387' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 1209' and pumped 70 sx cement w/200 # hulls. Cement circulated. POOH. Hooked to casing and pumped 20 sx cement at 250 psi. Hooked to braden head and pumped 10 sx cement at 150 psi then shut in.

GPS: 39.02798 -099.00748

Perfs:

Top	Bot	Thru	Comments
2938	2944		
2914	2923		
2636	2644		
2427	2438		
2340	2344		

Remarks: ALLIED CEMENTING TICKET # 055648

Plugged through: TBG

4/8/15 CKM

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3