

1100293

TO: STATE CORPORATION COMMISSION

4-13

API NUMBER 15-189-10,054, ~~0000~~
NE SW NE SEC. 24, T 34 S, R 37 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1982 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PEACHY #1 UNIT WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS 222.46

OPERATOR LICENSE # 5208

WELL TOTAL DEPTH 6845 FEET

OPERATOR: MOBIL OIL CORPORATION

PRODUCTION CSG: SIZE 5 1/2" @ 6844' WITH 400 SX

NAME AND PO BOX 2173

SURFACE CASING: SIZE 8 5/8" @ 1753' WITH 475 SX

ADDRESS LIBERAL, KS 67905-2173

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 13 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 6320-6334

1ST PLUG SPOT 25SX CEMENT WITH 3 HULLS OVER PERFS.

2ND PLUG AT 1780' WITH 50 SX CEMENT.

3RD PLUG AT 700' WITH 40 SX CEMENT.

4TH PLUG AT 40- TO SURFACE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 13 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 25 SX CEMENT WITH 3 HULLS OVER PERFS.

2ND PLUG AT 1780' WITH 50 SX CEMENT.

3RD PLUG AT 700' WITH 40 SX CEMENT.

4TH PLUG AT 40' TO SURFACE WITH 10 SX CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1925' OF 5 1/2" CASING.
IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 5-7-99

SIGNED Gary Winters (TECHNICIAN)

FORM CP-2/3

WV. NO. 60927
CONSERVATION DIVISION
Wichita Kansas

5-04-99