

6-090473

12-15

201

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,417-00-00

SE SE SE /4 SEC. 17, 15 S, 29 W
560 feet from S section line
560 feet from E section line

Operator license# 5316 Lease York well # 1

Operator: Falcon Exploration, Inc. County Gove

Address: 125 N. Market, Suite 1075 Well total depth 4320 feet
Wichita, Kansas 67202 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 345 feet

140.40

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Blue Goose Drilling Company License# 5104

Address: Great Bend, Kansas

Company to plug at: Hour: AM Day: 11 Month: December Year: 1991

Plugging proposal received from: Martin Miller

Company: Blue Goose Drilling Company phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1930 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 870 feet " 100 " Mousehole: sacks

3rd plug @ 395 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sks.

5th plug @ feet "

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 8:30 PM, Day: 15, Month: December, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 190sx 60/40 pozmix w/ 6% gel and 1 sx celloflake or flowcel.

Remarks: Elevation: 2496 GL, Anhydrite depth: 1912 - 1940 feet

Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did [] / did not [X] observe the plugging.

Ed Schumacher

Ed Schumacher P.I.R.T. III
(agent)

INVOICED

DATE 1-9-92

INV. NO. 34288

File S

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1991
CONSERVATION DIVISION
Wichita, Kansas