

6 070364

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13-063-20, 986-00-00
SE-SE-SW, SEC. 4, T 15 S, R 28 E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067Operator: Da Mar Resources, Inc.Name & Address And McDonald-WallacePetroleum Co Inc. P.O. Box70 Nags, No. 67601230 feet from S section line2120 feet from E section lineLease Name Coberly Well # "M" #1County Gove 141.05Well Total Depth 4240 feetConductor Pipe: Size 0 feetSurface Casing: Size 8 5/8 feet 302Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒Other well as hereinafter indicated Tog #948Plugging Contractor Drilling Oil Inc. License Number 5145Address R.R. Victoria, Kans.Company to plug at: Hour: 2:00 PM Day: 6th Month: July Year: 19 85Plugging proposal received from Dan Schippers(company name) Da Mar Resources, Inc. (phone) 913-625-0020were: 8 5/8" - 302' ES. CUL 1/190^{SK} Common duck Set, Dry filled Out.Order 210^{SK} 60/40 Pozmix Gcl - Ca-Cl, 1^{SK} shale and 8 5/8" Plug.spot with Drill stem, Recondition Hole (4⁵ viscosity) heavy Mud Between All Plugs.Mud Condition, Weight 10.1, Viscosity 44, No Circulation Problems, No ReducibleMiss Well, ELV. 2548, Only 1968.Plugging Proposal Received by Marion Schmitt
DOIC (TECHNICIAN)Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒Operations Completed: Hour: 6:30 PM Day: 6th Month: July Year: 19 85ACTUAL PLUGGING REPORT Order 210^{SK} 60/40 Pozmix Gcl - Ca-Cl, 1^{SK} shale and 8 5/8" Plug.spotted with Drill stem, Reconditioned Hole (4⁵ viscosity) heavy Mud Between All Plugs.1st Plug @ 1980' 1/30^{SK} ant, 2nd Plug @ 960' 1/100^{SK} ant 1/1^{SK} Cello3rd Plug @ 310' 1/50^{SK} ant, 4th Plug ^{solid bridge} shale, Plug @ 40' 1/0^{SK} ant.10^{SK} in Rat Hole, (circulate) 10^{SK} in Mouse Hole (circulate)Cemented by Allied Cnt.Remarks: RECEIVED
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-85INV. NO. 9068CONSERVATION DIVISION
Wichita, KansasSigned Marion Schmitt
DOIC (TECHNICIAN)