

TO: **STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202**

API Well Number: 15-063-20562-00-00
Spot: CSESE Sec/Twnshp/Rge: 35-15S-27W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: OWENS Q Well Number: 1
County: GOVE Total Vertical Depth: 4520 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 340 250 SX CMT
Production: Size 4.5 feet: 4519
Liner: Size _____ feet: 8146.90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2001 4:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 799-1000

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/31/2001 5:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 340' w/250 sxs cwc. 4 1/2" set at 4519' with cement N/A.
PBTD 4375'.
Prod. Perfs 4315' - 4428'.
Squeezed 4 1/2" with 200 sxs cement blend with 190# hulls mixed in to Max. P.S.I. 600# . Held.
Squeezed 8 5/8" with 10 sxs cement blend to Max. P.S.I. 500#.

RECEIVED

AUG 28 2001

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANI.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-29-01

INV. NO. 2002060302

AUG 07 2001

DONALD C. SLAWSON &
 AMERICAN ENERGIES
 200 DOUGLAS BUILDING
 WICHITA, KS 67202


REPLACEMENT CARD

35-15-27W
 C SE/4

#1 "Q" OWENS

CONTR SLAWSON DRG. CO., INC. CTY GOVE

GEOL JEFF STEWART FIELD WC (WHITNEY SW DISC)



ELV 2558 KB SPD 2/10/82 CARD ISSUED 6/24/82 IP P 126 BOPD & 2% WTR
 2552 GL
 ARI 15-063-20,562
 CHER 4315-4347 OA
 MISS 4405-4428 OA

LOG	Tops	Depth/Datum
ANH	1977+	581
B/ ANH	2012	546
HEEB	3770	1212
*TOR	3795	1237
LANS	3811	1253
STK	4059	1501
BKC	4118	1560
MARM	4144	1586
*ALT	4170	1612
PAW	4213	1655
*MYR STA	4260	1702
U CHER	4306	1748
L/ CHER	4340	1782
*CONG	4395	1837
MISS	4404	1846
OSAGE	4480	1922

8 5/8 " 340/250SX, 4 1/2 " 4519'
 DST (1) 3800-73 (SHAW, LANS) / 30-60-45-75, REC 1830' SG & MCSW, SIP 1252-1231#, FP 63-545 / 514-877#
 DST (2) 3885-3905 (LKC) / 30-60-45-75, REC 63' MCO (36% M, 64% OIL), 62' MCO (30% M, 70% OIL), 115' CL FROTHY GSY OIL, 10' SOCM, SIP 1189-1179#, FP 32-63 / 63-105#
 DST (3) 3965-94 (LKC) / 30-60-45-75, REC 80' OIL SPKD M, SIP 1043-1033#, FP 26-42 / 42-63#
 DST (4) 4057-81 (KC) / 30-60-30-30, REC 40' M, SIP 189-52#, FP 21-26 / 26-26#
 RTD 4520-1962
 LTD 4521-1963
 * SAMPLE TOPS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

INFO RELEASED: 6/2/83 - WAS OIL WELL - TIGHT HOLE
 (Over)

03010421

AUG 07 2001