

10-3

6 031439

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,341-00-00
NW NE SE, SEC. 15, T 11 S, R 31 W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

2310 feet from S section line
1105 feet from E section line

Operator Name: Ritchie Exploration Inc.
Address: 125 N. Market Suite 1000
Wichita, Ks. 67202

Lease Name Rodie Well # 3
County Cove 151.77

Well Total Depth 4670 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A xx

Other well as hereinafter indicated _____

Plugging Contractor White and Ellis Drilling Co. License Number 5420

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 3 Month: Oct Year: 19 90

Plugging proposal received from Don Demal

(company name) White and Ellis (phone) _____

were: 8 5/8 set at 327 w/175 sks cwc. Circ. hole w/no less than 36 vis mud w/no loss or gain in fluids. Balance plugs w/mud. Keep hole full. Order 190 sks 60/40 poz 6% gel 3% cc. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN) xx

Plugging Operations attended by Agent?: All _____ Part _____ None _____

Operations Completed: Hour: 10:00PM Day: 3 Month: Oct Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe. 25 sks at 2525.
100 sks at 1575 w/hulls
40 sks at 375
10 sks at 40 w/s.p.
Circ. 15 sks in rathole.

Remarks: elev. 2983 Anhy 2520 - 49

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 23 1990

INV. NO. 29702

J.S.

OCT 17 1990

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)