

11-16-87

6030994

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,149-00-00

SW NE NE, SEC. 26, T 14 S, R 29 W&E

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Foos Well # N 1

Operator: Pickrell Drilling Co.

County Gove 142.35

Name & Address 110 N. Market Suite 205

Well Total Depth 4380 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well X Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Great Bend, Ks.

Company to plug at: Hour: PM Day: 6 Month: Nov Year: 19 87

Plugging proposal received from Jack

(company name) Rockhold Eng. (phone)

were: 8 5/8" set at 300' w/185 sks. 4 1/2" set at 4373' w/175 sks. Squeezed at 3760' - 3761' w/180 sks. Order sand and Common Cement. Pull pipe. Order 200 sks A.T.L. 65/35 Poz 10% Gel 2% Dical Cement Blend 5 sks Hulls. Allied Cement Co. Walker Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:00PM Day: 6 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3700' w/4 sks Common Cement on sand w/bailer

7 shots recovered 1292' of 4 1/2" casing. Squeezed 8 5/8" casing w/200 sks A.T.L. Cement

Blend w/5 sks Hulls mixed in. Max Psi 600# Close in Psi 200#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

INVOICED

Signed Carl Goodrow (TECHNICIAN)

DATE 1-7-88

Carl Goodrow

FORM CP-2/3 LR Rev. 01-84

INV. NO. 19407

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
11-16-87