

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20752-00-00
Spot: CE2SE Sec/Twnshp/Rge: 24-15S-26W
1320 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: FLAX J Well Number: 1
County: GOVE Total Vertical Depth: 4500 feet

Operator License No.: 32047

Production Casing Size: 4.5 feet: 4490 175 SX CMT

Op Name: MICA ENERGY CORP.

Surface Casing Size: 8.625 feet: 329 225 SX CMT

Address: P. O. BOX 20707
OKLAHOMA CITY, OK 73156

\$146.25

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/04/2003 9:00 AM

Plug Co. License No.: 4072

Plug Co. Name: PLAINS INC

Proposal Rcvd. from: CLYDE D. TOWERY

Company: PLAINS INC

Phone: (785) 798-3995

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 500# hulls - 14 sxs gel.
Perfs 3980'-3984'; 4407'-4411'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 04/04/2003 1:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 4400' - pumped 33 sxs cement with 400# hulls.
Pulled to 3500' - mixed 14 sxs gel.
Pulled to 1920' - mixed 55 sxs cement to circulate to surface.
Pulled tubing and tied onto 4 1/2" casing.
Pumped 15 sxs cement to Max. P.S.I. 400#.
Hooked up to backside and pumped 25 sxs cement to Max. P.S.I. 300#.

Remarks: SWIFT SERVICES, INC. - TICKET #5413.

Plugged through: TBG

District: 04

Signed *[Signature]*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-15-03

INV. NO. 2003061409


APR 09 2003

DONALD C. SLAWSON
200 DOUGLAS BLDG. #1 "J" FLAX 24-15-26W
WICHITA, KS 67202. C E/2 SE

CONTR SLAWSON DRILLING CO. CITY GOVE

GEOL GEORGE MUELLER FIELD SPLITTER WEST

ELV 2504 KB SPD 3/22/84 CARD 7/19/84 IP P 103 B0 & 32 BWPD
2498 GL MISS 4407-4411



LOG	Tops	Depth-Datum	API 15-063-20,752
ANH	1926 +	578	8 5/8 " 329 / 225SX, 4 1/2 " 4499 / 175SX
B ANH	1965 +	539	DST (1) 3941-4005 (LKC 140' & 160' ZNS) / 30-60-45-75, 4
HEEB	3754-1250		INCH BLO THRU-OUT TST, 122' GIP, REC 101' GAS & MCO (60-
TOR	3774-1270		70% OIL, NW), 122' G & HOCM (25-40% OIL, NW), 61' G & OCM
LANS	3793-1289		(10% OIL, NW), SIP 1173-1160#, FP 21-21' / 21-21#
MUN CR	3946-1442		DST (2) 4031-4095 (LKC 200' & 220' ZNS) / 30-30-30-30, VWB,
STARK	4032-1528		REC 25' MUD, NS, SIP 1193-1006#, FP 21-21' / 21-21#
BKC	4092-1588		DST (3) 4282-4330 (FT SC) / 30-30-30-30, WB & DIED, REC 5'
PAW	4193-1689		MUD, NS, SIP 68-21#, FP 15-11' / 11-11#
FT SC	4298-1794		DST (4) 4320-4416 (MISS) / 30-60-45-75, FB THRU-OUT, REC
L CHER	4323-1819		10' CL GSY OIL, (GR 40'), 128' SOCM (10% OIL, 90% MUD), SIP
MISS	4390-1886		1235-1231#, FP 21-44' / 44-84#
MISS DOL	4406-1902		DST (5) 4416-4430 (MISS) / 30-60-45-75, WB, 15' GIP, REC 45'
PBTD	4447-1943		CL GSY OIL, (GR 40'), 62' MUD, W/SSD (20% WTR, 80% MUD),
LTD & RTD	4500-1996		SIP 1214-1193#, FP 21-30' / 42-63# (over)

DONALD C. SLAWSON #1 "J" FLAX 24-15-26W
C E/2 SE

MICT - CO, PF (MISS) 4407-11, W:4 SPF, SWB DRY TO 4447', SO ON TOOLS. AC 250G (15% FE) & 64.75 BBLs
LEASE WTR, SION, SWB DWN & REC 7.5 BF (8% WTR) / 4.5 HRS, AC 1000G (MOD-202), SWB DWN & REC 85
BF, SO, SION, FU:300' FL (577' WTR & 2423' OIL), SWB DWN & REC 14 BFPH (5% WTR) / 3.5 HRS; SET 2 3;
8 " TBG AT 1000', POP, P 103 B0 & 32 BWPD, 5/4/84

4407-11