

4-7

4-061062

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-063-21,500-00-00

S2 NW SE /4 SEC. 07, 15 S, 27 W
1650 feet from S section line
1980 feet from E section line

Operator license# 9860

Lease Jim Coberly Well # 1

Operator: Castle Resources, Inc.

County: Gove 140.73

Address: 1200 East 27th - Suite #C
Hays, Kansas 67601

Well total depth 4330 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 202 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:15 P.M. Day: 7 Month: April Year: 1997

Plugging proposal received from: Tom Alm

Company: Discovery Drilling, Inc. Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
KANSAS CORP COMM
1997 APR 0 4 11:11
4-10-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 4:15 P.M., Day: 7, Month: April, Year: 1997

Actual plugging report:

- 1st. Plug at 1990' w/25 sxs. Anhydrite 1962' - 1997'.
- 2nd. Plug at 910' w/100 sxs. Dakota 605' - 905'.
- 3rd. Plug at 255' w/40 sxs. Surface pipe to 202'.
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2505 GL

[] did not [X] observe the plugging.

[Signature]
DH (agent)

Form CP-2/3

INVOICED
DATE 4-11-97
INV. NO. 47908
4-7