

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20924-0000

LEASE NAME Gene Black

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 2 TWP. 34 RGE. 31 (E) or (W)

COUNTY Seward

Date Well Completed _____

Plugging Commenced 1/22/87

Plugging Completed 1/22/87

LEASE OPERATOR JORFORD CORPORATION

ADDRESS 1212 Thirteenth St., Suite 200, Lubbock,

PHONE# (806) 763-7831 TX 79401 OPERATORS LICENSE NO. 3145

Character of Well P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, KS (Richard Lacy)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation none Depth to Top _____ Bottom T.D. 6150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
St. Louis	Dry			8 5/8 24#	1562'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Hook up @ 3,000', pump H2O, 125 sks, 50/50 Poz 2% gel, pump H2O & displace w/mud; 1,590' pump H2O 50 sks 50/50 Poz 2% gel, pump H2O & displace w/mud; 660' pump H2O 40 sks 50/50 Poz 2% gel, displace w/H2O; push down plug at 40' pump 10 sks 50/50 Poz 2% gel; 15 sks 50/50 Poz 2% gel down rat hole; 10 sks

(If additional description is necessary, use BACK of this form.)

50/50 Poz 2% gel down mousehole.

Name of Plugging Contractor Sage Drilling Co., Inc. License No. 5421

Address 202 S. St. Francis, Wichita, KS 67202

STATE OF Texas COUNTY OF Lubbock, ss.

Larry Langerhans (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry Langerhans

(Address) 1212 13th St., Ste 200,
Lubbock, TX 79401

FEB 17 1987

CONSERVATION DIVISION

SUBSCRIBED AND SWORN TO before me this 11th day of February, 19 87

My Commission Expires: 1/21/89 CARLA LAKATTA Notary Public