

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20924-0001

LEASE NAME Black

WELL NUMBER 2-1

C S/2
SW NW Ft. from S Section Line

Ft. from E Section Line

SEC. 2 TWP. 34S RGE. 31W(E) or (W)

COUNTY Seward

Date Well Completed _____

Plugging Commenced 2-6-92

Plugging Completed 2-10-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Quinque Operating Company

ADDRESS P. O. Box 2738 Liberal, KS 67905-2738

PHONE#(316) 624-2578 OPERATORS LICENSE NO. 05225

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-6-92 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Marmaton Depth to Top 5131 Bottom 5137 T.D. 6150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil	5128	5154			
				8 5/8	1562	0
				4 1/2	5290	2835

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement & 1 sk. of hulls to 5000

Pump 50 sks. of cement from 1580 to 1480

Pump 35 sks. of cement from 600 to 500

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P. O. Box 506 Liberal, KS 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Quinque Operating Company

STATE OF Kansas COUNTY OF Seward, ss.

Michael Moore

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) X [Signature]

(Address) P. O. Box 2738 Liberal, KS 67905-2738



SUBSCRIBED AND SWORN TO before me this 25 day of February, 19 92

Beverly A. White

Notary Public

My Commission Expires: 11-27-95