

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20614 -0000

LEASE NAME Black

Plug bottom of well in order
to use 8 5/8" casing for a
Disposal well.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2-1

3300 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Sage Drilling Co., Inc.

SEC. 1 TWP. 34S RGE. 31 (E) or (W)

ADDRESS 202 S. St. Francis, Wichita, Ks 67202

COUNTY Seward

PHONE# (316) 263-6139 OPERATORS LICENSE NO. 5421

Date Well Completed 6/11/82

Character of Well oil Now it is a SWD in the
8 5/8" casing
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 4/4/88

Plugging Completed 4/6/88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Toronto Depth to Top 4323 Bottom 4331 T.D. 6040

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------------------|------|----|-------|--------|------------|
| St. Louis | Sli Oil & Water | 5962 | 73 | 8 5/8 | 1564 | none |
| St. Louis | Sli Oil, Sli gas & | 5924 | 52 | 5 1/2 | 6039 | 2610' |
| Chester | Sli Gas & Wtr | 5723 | 78 | | | |
| Toronto | Sli Gas, Oil, & Wtr | 4323 | 31 | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 2 sx of hulls and 30 sx of cement with 9 ppg mud to close off 4323 to 31 perfs. 9.0 ppg mud up to 1600'. 5 1/2" casing shoot off at 2610'. 50 sx cement plug from 1600' to 1500'. 8 5/8" CBP at 1500' with 10' cement on top. Well turned into SWD well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67901


STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles Casey Coats (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Casey Coats

(Address) 202 S. St. Francis, Wichita, Ks 67202-

SUBSCRIBED AND SWORN TO before me this 18 day of April, 19 88



RECEIVED
Peggy A. Clutter Notary Public

APR 18 1988

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84