

15-175-10209-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____
LEASE NAME Gene Black
WELL NUMBER "B" #1
535 Ft. from ~~XXXX~~ ^{North} Section Line
1980 Ft. from ~~XXXX~~ ^{West} Section Line
SEC. 1 TWP. 34S RGE. 34 (X) or (W)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texaco Inc
ADDRESS Box 2420, Tulsa, Ok
PHONE#(918) 560-6000 OPERATORS LICENSE NO. 5153

COUNTY Seward
Date Well Completed 8-14-62
Plugging Commenced 11-2-85
Plugging Completed 11-5-85

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
Which KCC/KDHE Joint Office did you notify? Dodge City - Paul Luthi
Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation St Genevieve Depth to Top 5793 Bottom 5824 T.D. 5894 PB-
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				9-5/8	1250	none
				5-1/2	5911	2602

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump 25 sks cement & 2 sks hulls 5888-5600'; 25 sks cement & 1 sk hulls 4422-4422-4100'; pump 50 sks cement 1280-1180; 30 sks cement 600-500; Put 10 sks cement @ 40-0'; cut off and cap 9-5/8" 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling License No. 6547
Address Box 506, Liberal, Ks 67901

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

R. W. BLOHM (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. W. Blohm
(Address) Box 2420, Tulsa, Ok 74102
R. W. BLOHM, Ass't Dist Mgr.

SUBSCRIBED AND SWORN TO before me this 23rd day of Dec, 19 85
Devon M. Coburn
Notary Public

My Commission Expires: 8/31/88

STATE CORPORATION COMMISSION
12-26-85
DEC 26 1985