

15-119-10339-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 - N/A

LEASE NAME Adams "D"

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

NE NW SE Ft. from S Section Line

         Ft. from E Section Line

SEC. 35 TWP. 34 SRGE. 30W (E) or (W)

COUNTY Meade

LEASE OPERATOR Graham - Michaelis Corp.

ADDRESS P.O. Box 247 Wichita, Kansas 67201

PHONE (316) 264-8394 OPERATORS LICENSE NO. 5134

Date Well Completed         

Character of Well Gas

Plugging Commenced 9-20-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-23-94

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes 9-20-94

Which KCC/KDHE Joint Office did you notify? Dodge City Lacey

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.O. 5959

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1276	0
				5 1/2	5959	2742

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Pump 25 sks. of cement & 2 sks. of hulls to 5700'

Pump 50 sks. of cement from 1300 to 1200

Pump 50 sks. of cement from 600 to 500

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Sedgwick, ss.

DARON PATTERSON

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Daron M. Patterson


(Address) P. O. Box 247, Wichita, KS 67201

OCT 05 1994

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1994

Aldine M. Johnson  
Notary Public

My Commission Expires         



RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-119-10339-0000

THOMAS & BREWER #2 ADAMS 'D' 35-34-30W  
 NE NW SE  
 Contr. BENNETT & ROBERTS MEADE County  
 E 2564RB Comm. Comp. 10-30-59 IP 217 BOPD &  
 1,500,000 CFG

Tops	Depth	Datum
<i>marm</i>	5240	-2076
MORR	5816	-3252
CHEST	5918	-3354
ID	5959	-3395

Casing  
 8" 1276  
 5" 5958  
 PERF 12/5906-09: 16/5896-5900: 20  
 5879-84: ACID 1500: SWB 2 BOPH &  
 G: FRAC: FLO 20-30 BOPH & G:  
 PLUG 5869: 20/5847-51: 4/5836-37:  
 ACID 1000: FLO 10 BOPH

ADAMS RANCH


5240  
 2564  
 3252  
 2676

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 12 1994

WICHITA, KANSAS