

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Meade

County. Sec. 34 Twp. 34 Rge. 30 (E) (W)

Location as "NE/CNW/SW" or footage from lines. C SE SW

Lease Owner. S & S Pipe & Supply Bulldog Pipe & Supply

Lease Name. FOX Well No. 1

Office Address. 309 Mayo Building Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_

Plugging commenced 7-2-68 \_\_\_\_\_ 19\_\_

Plugging completed 7-7-68 \_\_\_\_\_ 19\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 6140 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	2603	None
				5 1/2	None	2702

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Moved tubing.

Dumped 20 sacks of cement at 5800'. Cleaned out cellar. Welded on 5 1/2" collar. Working pipe.

Working pipe. Shot pipe at 5000' - 4500' - 4000'.

Working pipe. Shot pipe at 3500' - 3000' - 2900' - 2800' and 2715'.

Pulling pipe. Cut off 8 5/8 casing and welded on nipple. Pulling on 8 5/8" casing. Set rock bridge at 800'. Dumped 36 sacks of cement. Mudded hole and rock bridge. Capped well with 16 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1968

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 16 day of July, 1968

My commission expires May 27, 1969

[Signature]  
Notary Public.

15-119-00090-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company: THOMAS & BREWER  
Farm: Fox No. 1

SEC. 34 T. 34 R. 30W  
C SE SW

Total Depth. 6140'  
Comm. 12-4-50 Comp. 12-28-50  
Shot or Treated.  
Contractor. Garvey Drig.  
Issued. 7-4-59

County Meade KANSAS



Elevation. 2592' DF

CASING:  
8 5/8" 2603' cen w/700 ex.  
5 1/2" 5975' cen w/110 ex.

Production. 5,265,000 CPG

Figures indicate Bottom of Formations.

gyp rock & sand	105
sand & shale	520
red bed	600
red bed & gyp	1040
shale & shells	1370
red shale & gyp	1515
shale & gyp	2245
lime	2735
chalky lime	2868
lime & sand	2980
lime	3606
chalky lime	3712
lime & shale	3835
shale	4050
lime	4065
shale w/line strks	4245
shale	4450
shale & lime	4625
lime	5230
lime & shale	5285
lime	5505
lime & shale	5563
lime	5725
lime & shale	5860
shale & sand	5910
shale & lime	6140
Total Depth	

TOPS: SCOUT	
Council Grove	3047
Toronto	4434
Lansing	4548
Marmaton	5230
Cherokee	5430
Morrow	5807
Chester	5943

RECEIVED  
STATE COMMISSION ON GEOLOGICAL SURVEY  
JUNE 1959  
CONSERVATION DIVISION  
Topeka, Kansas