

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15119-20677-0000

LEASE NAME Adams

WELL NUMBER 1-34

SPOT LOCATION SW NW

SEC. 34 TWP. 34S RGE. 30 (E) or (W) (W)

COUNTY Meade

Date Well Completed 12-28-84

Plugging Commenced 3-30-85

Plugging Completed 4-3-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bracken Exploration Company

ADDRESS 5101 N. Classen Blvd., OKC 73118

PHONE # (405) 840-5541 OPERATORS LICENSE NO. 9886

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District I - Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Marmaton Depth to top 5321' bottom 5330' T.D. 5430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Marmaton</u>		<u>5321</u>	<u>5330</u>	<u>8-5/8</u>	<u>1506</u>	<u>None</u>
<u>Kansas City</u>		<u>4897</u>	<u>4932</u>	<u>4-1/2</u>	<u>5429</u>	<u>3808</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. CIBP's set @ 5280' & 4850' with 10' cement on each. Load hole with 9 # mud. Shot pipe at 4200' & 3800'. Pipe free at 3808'. LD 55 jts 4-1/2" casing. Spot 30 sxs plug from 1550'. Pull casing to 725'. Spot 30 sxs plug. Pull remainder of casing. Spot 10 sxs plug from 40-0'. Cut off head & weld on ID plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent Casing Pullers License No. 6547
Address Box 506, Liberal, KS 67901

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

C. Michael Ming (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me PROCEIVED

STATE CORPORATION COMMISSION

(Signature) C. Michael Ming

(Address) 5101 N. Classen Blvd., OKC

MAY 8 1985

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 85

Zelda Hartow
Notary Public

My Commission expires: 3-22-88