

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Meade SEC. 32 TWP. 34S RGE. 30W E/W  
Location as in quarters or footage from lines:  
2012' FWL 1980' FSL


Lease Owner Quinque Oil & Gas Producing Co.  
Lease Name Adams Well No. 2-32  
Office Address 18 West 3rd. Street Liberal, Kansas 67901  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed \_\_\_\_\_  
Application for plugging filed 3-31-81  
Plugging commenced 5-12-81  
Plugging completed 5-14-81  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 6375

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1296	none
				4 1/2	5600	2558

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Pump 1 sk. of hull's & 25 sks. of cement @ 4428 to 4200	RECEIVED
Spot 40 sks. of cement @ 2558 to 2458	STATE CORPORATION COMMISSION
Spot 50 sks. of cement @ 1250 to 1150	
Spot 25 sks. of cement @ 600 to 500	JUN - 11 1981
Put 10 sks. of cement @ 40 to 0	6-1-81
	CONSERVATION DIVISION
	Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511

STATE OF Kansas COUNTY OF Seward, ss.

Janice Heckman (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Janice Heckman  
18 West Third Street, Liberal, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May, 19 81



Cecil Corbin  
Notary Public.

My Commission expires:

# WELL LOG

COMPANY Quinque Oil & Gas Producing Co.

SEC. 32-34S-30W

FARM Adams

NO. 2-32

LOC. NE SW


TOTAL DEPTH 6375

COUNTY Meade, Ks.

COMM. 1-30-81

COMP. 2-11-81

CONTRACTOR Zenith Drilling Corporation



Ran <sup>CASING</sup> 34 jts. 23# 8 5/8" casing, set at 1296' with 750 sacks cement

Ran 139 jts. 10.5# & 13 Jts. 11.6# 4 1/2" csg., set at 5600' with 300 sacks cement

### PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

220	Surface Sand
1150	Surface Sand & Red Bed
1296	Red Bed & Anhydrite
2350	Red Bed & Shale
2725	Shale
3050	Shale & Lime
6345	Lime & Shale
6375	Lime

RECEIVED  
KANSAS OIL & GAS COMMISSION

APR - 1 1981

REGISTRATION DIVISION  
Topeka, Kansas

State of KANSAS }  
County of SEDGWICK } SS

I, Emmet E. Hall of Zenith Drilling Corporation

upon oath state the above and foregoing is a true and correct copy of the log of the Adams #2-32 well.

Subscribed and sworn to before me this 17th day of February, 1981.

My Commission Expires: Dec. 15, 1984

Sharon R. Allen  
Sharon R. Allen NOTARY PUBLIC