

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20664 ^{22.0001}

LEASE NAME Adeline

WELL NUMBER 1-22

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 22 TWP. 34 SRGE. 32 (X) or (W)

COUNTY Seward

Date Well Completed 9-29-82

Plugging Commenced 10-16-95

Plugging Completed 10-18-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Quinque Operating Co.

ADDRESS P. O. Box 2738 Liberal, KS 67905-2738

PHONE# (316) 624-2578 OPERATORS LICENSE NO. 5225

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-16-95 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Upper Morrow Depth to Top 5992 Bottom 5774 T.D. 6550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Miss/Ste Gen 6408	Limestone	1200	0	8 5/8		
Miss/Chester 5992	Limestone	6347	0	4 1/2		2830
Upper Morrow 5774	Sand					
Morrow 5752	Shale					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from ___ feet to ___ feet each s
Mixed 2 sx hulls to 20 sx cmt. to plug perfs from 5781 to 5581. Recovered 2830 4 1/2.
Mixed 40 sx cmt. plug from 1500 to 1400. Mixed 40 sx from 1230 to 1130 @ bottom of 8 5/8.
Mixed 40 sx from 650 to 550. Mixed 10 sx 33 to 3. Cut off & capped 8 5/8 3 ft. below
ground level. Used mud between all plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Quinque Operating Company

STATE OF Kansas COUNTY OF Seward, ss.

Michael Moore President of Quinque Operating Company (Employee of Operator) or (Operator:
above-described well, being first RECEIVED sworn on oath, says: That I have knowledge of the fac
statements, and matters NOTED the log of the above-described well as filed
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Michael Moore, President
P. O. Box 2738 Liberal, KS 67905



NOV - 2 1995

11-2-95

AND SWORN TO before me this 31 day of October, 19 95

Beverly A. Stahle

Beverly A. Stahle Notary Public

My Commission Expires: 11-27-99