

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200, Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-20,891-0000

LEASE NAME Stefan

WELL NUMBER 1-21

660' Ft. from S Section Line

3300' Ft. from E Section Line

SEC. 21 TWP. 34 RGE. 32 or (W)

COUNTY Seward

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-13-91

Plugging Completed 5-17-91

LEASE OPERATOR Chaparral Energy Inc.

73114

ADDRESS 10701 N. Broadway Ext. Oklahoma City, Ok.

PHONE# (405) 749 9992 OPERATORS LICENSE NO. 30051

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-10-1991 (date)

by Mr. Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 85798' Bottom 5972' T.D. 6200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1557'	0'
Production				4 1/2"	6200'	4237'

RECEIVED  
STATE CORPORATION COMMISSION  
5-31-91  
4237 MAY 21 1991

Describe in detail the manner in which the well was plugged, indicating where cement was placed and the method or methods used in introducing it into the hole. If cement plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pump 2 sks hulls & 20 sks Cement to 5400' Pressured to 750 lbs.  
Pump 50 sks cement 1580' to 1430' Mud 1430' to 800'-Pump 40 sks cement 800' to 700'-Mud 700' to 40'- Put bridge & 10 sks cement 40' to 5'  
Cut off 8 5/8" 5' below ground level & cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling License No. 6497

Address Box F, Sublette, Kansas 67877

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chaparral Energy Inc.

STATE OF Kansas COUNTY OF Haskell, ss.

I Edgar J. Eves (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Bx. F, Sublette, Ks. 67877



SUBSCRIBED AND SWORN TO before me this 30<sup>th</sup> day of May, 19 91

Sondra L. Eves  
Notary Public

My Commission Expires: 12-6-92