

10-31 15-129-00036-0000

1 020261

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E11,602
C. SE. NE, SEC. 17, T. 34 S, R. 43 W. ~~43~~
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67501-0351

Lease Name ISU Well # 14
County Morton 141.70
Well Total Depth 4360 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1275

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 30 Month: 10 Year: 19 89

Plugging proposal received from Don Horton

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4356' PBD 4356' Perfs at 4272-4314' 4300-4314' Est. TOC 4030'

- 1st plug run 2 sx hulls and 30 sx cement at perfs,
- 2nd plug load hole with mud, pump 25 sx cement at 2605',
- 3rd plug pump 50 sx cement at 1200-1050',
- 4th plug pump 35 sx cement at 650-480', 5th plug pump 10 sx cement at 50-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 4 p.m. Day: 31 Month: 10 Year: 19 89

- ACTUAL PLUGGING REPORT
- 1st plug ran 2 sx hulls and 30 sx cement at perfs,
 - 2nd plug loaded hole with mud and pumped 25 sx cement at 2605',
 - 3rd plug pumped 50 sx cement at 1200-1050',
 - 4th plug pumped 35 sx cement at 650-480',
 - 5th plug pumped 10 sx cement at 50-0'.

RECEIVED
STATE CORPORATION COMMISSION
NOV - 7 1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargents. Recovered 2626' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(copy of this report) observe this plugging.

DATE 11-13-89

Signed Glenn R Barlow
(TECHNICIAN)

INV. NO. 26376
10-31