

9-29-87 15-129-10493-0000
Docket #E-11,602

To: 1 061018
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 11/9/56
C SW SW, SEC. 17, T 34 S, R 43 (W/E)
660 feet from S section line
4620 feet from E section line
Interstate Unit
Lease Name _____ Well # 20

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

County Morton 140.09
Well Total Depth 4310 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 17 feet 1138

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 29 Month: 9 Year: 19 87

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4304' PBD 4100' w/CIBP Perfs at 4225-38'
1st plug set CIBP at 4100' and dump 25 sx cement on top,
2nd plug pump 30 sx cement at 2000', 3rd plug pump 40 sx cement at 1200',
4th plug pump 35 sx cement at 650', 5th plug pump 10 sx cement at 50-0'.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7 p.m. Day: 29 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' and dumped 25 sx cement on top,
2nd plug pumped 30 sx cement at 2000',
3rd plug pumped 40 sx cement at 1200',
4th plug pumped 35 sx cement at 650',
5th plug pumped 10 sx cement at 50-0'.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1987

Remarks: Used common cement by Sargent's. Recovered 2030' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-6-87
INV. NO. 18370

Conservation Division
Wichita, Kansas
Signed Paul A. Luthi (TECHNICIAN)

9-29 OCT 29 1987