

To: 1 051551
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-29

15-129-10484-0000 248
API NUMBER 15- Docket #E-21,363

SW SE, SEC. 17, T. 34 S, R. 43 W/R
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549

Lease Name Interstate Unit Well # 22
County Morton 141.70

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Well Total Depth 4360 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7 feet 1198

Abandoned Oil Well _____ Gas Well _____
Input Well ^{ENHR} X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 27 Month: 4 Year: 19 92

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

Work: 4 1/2" at 4310' w/400 sx cement, PBD 4310', Perfs at 4242-58'

1st plug set CIBP at 4200' and dump 15 sx cement on top,

2nd plug pump 30 sx cement at 2210',

3rd plug pump 30 sx cement at 1250',

4th plug pump 30 sx cement at 650', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4 p.m. Day: 29 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4200' with 15 sx cement on top, pumped with tubing,

2nd plug hole loaded with mud and pumped 30 sx cement at 2200',

3rd plug pumped 30 sx cement at 1225',

4th plug pumped 30 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2210' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 5-14-92

INV. NO. 35233

Signed Richard M. Lacey (TECHNICIAN) RECEIVED CORPORATION COMMISSION MAY 6 1992
CONSERVATION DIVISION
Wichita, Kansas
WDDP-213
Rev. 01-84