

15-129-10398-0000

To: 1 020456 4-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- E-11,602  
C NW NW, SEC. 17, T. 34 S, R. 43 W/E  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Interstate UniWell # 7  
County Morton  
Well Total Depth 4350 141.37 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1229

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547  
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 11 a.m. Day: 17 Month: 4 Year: 1992

Plugging proposal received from Don Horton  
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 4350' w/150 sx cement, PBTD 4316', Perfs at 4284-4315.5'  
1st plug pump 1 sx hulls and 15' sx cement, displace with mud,  
2nd plug shoot pipe off at 2405', load hole with mud, pump 25 sx cement at 2400',  
3rd plug pump 30 sx cement at 1250',  
4th plug pump 30 sx cement at 650', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 21 Month: 4 Year: 1992

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 15 sx cement, displaced with mud,  
2nd plug shot pipe at 2405', loaded hole with mud, and pumped 25 sx cement at 2400',  
3rd plug pumped 30 sx cement at 1250',  
4th plug pumped 30 sx cement at 650',  
5th plug pumped 10 sx cement at 40 to -4',  
All plugs displaced with mud.

Remarks: Used common cement by Sargent's. Recovered 2405' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAY 06 1992  
INV. NO. 35159

Signed Glenn R Barlow (TECHNICIAN)

RECEIVED  
MAY 1 1992  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas