

1 020847 3-17

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-20,458-0000  
C SW, SEC. 17, T 34 S, R 43 W/E  
1320 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate B Well # 6

Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67905-0351

County Morton  
Well Total Depth 1335 43.39 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 17 Month: 3 Year: 19 95

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

was: 4 1/2" at 1334' w/500 sx cement, PBSD 1330', Perfs at 1242-50, 1256-58, 1266-76'

1st plug load hole with mud and spot one sx hulls and 20 sx cement at perfs,

2nd plug pump 20 sx cement at 500-300',

3rd plug pump 5 sx cement at 40-0' in 4 1/2" & 8 5/8".

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 17 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug loaded hole with mud and spotted 1 sx hulls and 20 sx cement at perfs,

2nd plug pumped 20 sx cement at 500-300',

3rd plug pumped 5 sx cement in 4 1/2" from 40-0' and 8 5/8" to surface.

Remarks: Used common cement by Sargent & Horton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
Observe this plugging.

DATE MAR 29 1995

INV. NO. 42480

Signed Glenn R Barlow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 29 1995  
CONSERVATION DIVISION