

To: 1 020452  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-13 15-129-10496-0000  
API NUMBER 15 - Drill Completion Date 8/18/56 128

SE SW, SEC. 17, T. 34 S, R. 43 W/E  
660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 21

Operator: Anadarko Petroleum Corporation  
Name &

County Morton

Address P.O. Box 351  
Liberal, KS 67905-0351

Well Total Depth 4260 138.45 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1138

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 2 p.m. Day: 9 Month: 4 Year: 19 92

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 4260' w/400 sx cement. PBD 4213'. Perfs at 4203-13'

1st plug pump 1 sx hulls and 15 sx cement at perfs, displace with mud, shoot pipe off and circulate hole with mud,

2nd plug pump 25 sx cement at 2200', 3rd plug pump 35 sx cement at 1170',

4th plug pump 25 sx cement at 650', 5th plug pump 10 sx cement at 40 to--4'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 13 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 15 sx cement at perfs, displaced with mud. Shot pipe off and circulated hole with mud,

2nd plug pumped 25 sx cement at 2200', 3rd plug pumped 35 sx cement at 1170',

4th plug pumped 25 sx cement at 650', 5th plug pumped 10 sx cement at 40 to--4'

Mud used to displace all plugs.

Remarks: Used common cement by Sargent's. Recovered 2216' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

**INVOICED**  
observe this plugging.

DATE 3-28-92

Signed Glenn R Barlow  
(TECHNICIAN)

INV. NO. 35077

KANSAS RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1992  
CONSERVATION DIVISION  
WICHITA, KS