

1 020079

6-2-87¹⁵-129-10502-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 12/22/56
C NW SW, SEC. 16, T 34 S, R 43 W/EX
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67901

Lease Name Interstate Unit Well # 18
County Morton 139.75
Well Total Depth 4300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7" feet 1179

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 1 Month: 6 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4300' PBSD 4110' Perfs at 4184-4227'

1st plug 20 sx cement on top of CIBP with tubing,

2nd plug at 1280' with 50 sx cement, 3rd plug at 650' with 25 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 2 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement on top of CIBP with tubing,

2nd plug pumped 50 sx cement at 1280',

3rd plug pumped 25 sx cement at 650',

4th plug pumped 10 sx cement at 40-0'. Mud between all plugs.

JUN 9 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.
Formerly Panhandle Eastern Pipe Line Co.

Signed Glenn R. Barlow
(TECHNICIAN)

DATE 6-9-87 Interstate "C" 05

INV. NO. 17195 6-2