

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20558-00-00
Spot: SESWSW Sec/Twnshp/Rge: 16-34S-43W
10 feet from S Section Line, 1300 feet from E Section Line
Lease/Unit Name: INTERSTATE UNIT Well Number: 88
County: MORTON Total Vertical Depth: 4250 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet: _____
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1192 WITH 600 SX CMT 8138.13
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 4248 WITH 105 SX CMT
HOUSTON, TX 77060 Liner: Size _____ feet: _____

Well Type: EOR UIC Docket No: E11602.3 Date/Time to Plug: 10/18/2001 11:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: BOTTOM PLUG PUT 10 SX CMT ON TOP. LOAD HOLE WITH MUD. 1ST PLUG AT 1220' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/18/2001 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PERFS AT 4133-4150'. CIBP ALREADY SET AT 4100'. RAN IN HOLE WITH 1 1/2" TUBING TO 4100' & SPOT 10 SX CMT ON CIBP. LOAD HOLE WITH MUD. 1ST PLUG AT 1220' WITH 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 600' & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULLED OUT OF HOLE TO 40' & PUMP 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1228' OF 5 1/2" CASING.
Plugged through: CSG

District: 01 Signed: Jim Holland PART II (TECHNICIAN)
RECEIVED
OCT 25 2001
KCC WICHITA
INVOICED
DATE 10-26-01
INV. NO. 2002060850
OCT 22 2001
Form C-10