

To: **1020801**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-20

Docket

API NUMBER **15-** **E-21,363** **15-129-10494-0001**

C SW SW, SEC. **16**, T **34** S, R **43** WEX

**660** feet from S section line

**660** feet from WEX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # **4549**

Operator: **Anadarko Petroleum Corporation**

Name & Address **P.O. Box 351**

**Liberal, KS 67905-0351**

Lease Name **Interstate Unit** Well # **24**

County **Morton**

Well Total Depth **4319** **140.36** feet

Conductor Pipe: Size **7** feet

Surface Casing: Size **7** feet **1212**

Abandoned Oil Well **X** Gas Well **X** Input Well **X** SWD Well **X** O&A **X**

Other well as hereinafter indicated **X**

Plugging Contractor **Sargent & Horton Plugging, Inc.** License Number **31151**

Address **Rt. 1, Box 49BA, Tyrone, OK 73951-9731**

Company to plug at: Hour: **16** Day: **9** Month: **94**

Plugging proposal received from **Don Horton**

(company name) **Sargent & Horton Plugging, Inc.** (phone) **405-854-6575**

were: **4 1/2"** at **4277'** w/550 sx cement, PBTD **4240'**, Perfs at **4198-4228, 4230-37'**

1st plug run tubing, pump 10 sx cement on top of CIBP at **4120'**,

2nd plug pump 50 sx cement at **1250'**, 3rd plug pump 40 sx cement at **650'**,

4th plug pump 10 sx cement at **34 to -4'**.

Plugging Proposal Received by **Glenn Barlow**  
(TECHNICIAN)

Plugging Operations attended by Agent?: All **X** Part **X** None **X**

Operations Completed: Hour: **20** Day: **9** Month: **94**

ACTUAL PLUGGING REPORT 1st plug ran tubing and pumped 10 sx cement on top of CIBP at **4120'**,

2nd plug pumped 50 sx cement at **1250'**,

3rd plug pumped 40 sx cement at **650'**,

4th plug pumped 10 sx cement at **34 to -4'**.

Gel mud between all plugs.

Remarks: **Used common cement by Sargent & Horton. Recovered 1628' of 4 1/2" casing.**  
(If additional description is necessary, use BACK of this form.)

I (operator) did not observe this plugging.

Signed **Glenn Barlow**  
(TECHNICIAN)

INVOICED

DATE **10-6-94**

INV. NO. **41316**