

1 020080

6-5-87 15-129-10508-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion 4/24/57

C NW NW, SEC. 16, T 34 S, R 43 W/EX  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 11

Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67901

County Morton 141.38

Well Total Depth 4350 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 7" feet 1200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 3 Month: 6 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4340' PBTB 4110' Perfs at 4246-4270', 4223-4228'  
1st plug set CIPB at 4110' with 20 sx cement on top, run with tubing, 2nd plug at 2390'  
with 30 sx cement, 3rd plug at 1300' with 50 sx cement, 4th plug at 650-470' with 25 sx  
cement, 5th plug at 65-0' with 10 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug CIPB at 4110' with 20 sx cement on top, run with tubing,  
2nd plug at 2390' with 30 sx cement,  
3rd plug at 1300-1100' with 50 sx cement,  
4th plug at 650-470' with 25 sx cement,  
5th plug at 65-0' with 10 sx cement. Heavy mud between each plug.

JUN 9 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2400' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
(if applicable) observe this plugging.  
Formerly Panhandle Eastern Pipe Line Co.

Signed Glenn R Barlow  
(TECHNICIAN)

DATE 6-9-87 Interstate "C" No. 09

INV. NO. 17194  
6-5