

1 020760

S-20

API NUMBER 15-

15-129-10499-0001
Docket #E-21,363

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE SW, SEC. 16, T 34 S, R 43 W/X
660 feet from S section line
1980 feet from W & section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4549

Lease Name Interstate Unit Well / 25

Operator: Anadarko Petroleum Corporation

County Morton

Name:

Address P.O. Box 351

Well Total Depth 4290 139.42 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 7" feet 1168

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 3 p.m. Day: 17 Month: 5 Year: 1994

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6575

w/c: 4 1/2" at 4276' w/200 sx cement, PBTD 4239', Perfs at 4176-84, 4190-4202, 4211-14'

1st plug pump 1 sx hulls and 20 sx cement at perfs, tag cement,

2nd plug pump 25 sx cement at 2330', 3rd plug pump 45 sx cement at 1260',

4th plug pump 25 sx cement at 660', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 11 a.m. Day: 20 Month: 5 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, tagged top
of cement at 3970',

2nd plug pumped 25 sx cement at 2330',

3rd plug pumped 45 sx cement at 1260',

4th plug pumped 25 sx cement at 660',

5th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargent & Horton Plugging. Recovered 2013' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAY 30 1994

Signed

Glenn R. Barlow
(TECHNICIAN)

INV. NO. 40506

S-20

FORM C
Rev.