

To: 1 020453 4-16  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15-129-40491-0000 1874  
API NUMBER 15-Drill Completion Date 3/30/57

NE SW, SEC. 16, T. 34 S, R. 43 W/4  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # C 1 19  
County Morton 141.21  
Well Total Depth 4345 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 7 feet 1200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 11 a.m. Day: 14 Month: 4 Year: 1992

Plugging proposal received from Don Horton  
(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 4327' w/150 sx cement, PBD 4220', Perfs at 4201-06'  
1st plug pump 1 sx hulls and 15 sx cement at perfs, displace with mud,  
2nd plug load hole with mud and pump 25 sx cement at 2400',  
3rd plug pump 30' sx cement at 1240', 4th plug pump 30 sx cement at 650',  
5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 16 Month: 4 Year: 1992

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 15 sx cement at perfs, displaced with mud,  
2nd plug loaded hole with mud and pumped 25 sx cement at 2400',  
3rd plug pumped 30 sx cement at 1240',  
4th plug pumped 30 sx cement at 650',  
5th plug pumped 10 sx cement at 40 to -4'.

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 24 1992  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used common cement by Sargent's. Recovered 2410' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (and my employees) observe this plugging.

DATE MAY 04 1992

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 25106