

020238

6-27 15-129-10450-0000
15-129-10450-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 7/14/61

C NW NW, SEC. 32, T 34 S, R. 43 W/E

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 71

Operator: Anadarko Petroleum Corporation
Name &

County Morton 140.08

Address P.O. Box 351

Well Total Depth 4310 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1242

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 2:15 p.m. Day: 21 Month: 6 Year: 19 89

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4309' PBSD 4310' Perfs at 4202-16' Elevation 3539' GL

1st plug set CIBP at 4110' with 20sx cement on top,

2nd plug pump 30 sx cement at stub, 3rd plug pump 40 sx cement at 1300',

4th plug pump 35 sx cement at 500',

5th plug pump 25 sx cement at 80-0'.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 27 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4110' with 20 sx cement on top,

2nd plug loaded hole with mud, pumped 30 sx cement at 2220',

3rd plug spotted 40 sx cement at 1300-1200',

4th plug pumped 35 sx cement at 500-400',

5th plug pumped 25 sx cement at 80-0'.

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 - 5 1989
7-5-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2220' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-6-89

Signed *Richard W. Lacey*
(TECHNICIAN)

INV. NO. 25213
6-27 SEP 11 1989