

1 020831 12-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-21,220 - 0000
NE NE SE SW, SEC. 32, T. 34 S, R. 43 W/EX
1250 feet from S section line
2800 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Linscott B Well # 9
County Morton 97.50
Well Total Depth 3000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 679

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 15 Month: 12 Year: 19 94

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 2976' w/355 sx cement, CIBP at 2875', Perfs at 2693-2850'

1st plug pump 4 sx hulls and 25 sx cement at perfs, pressure up,

2nd plug pump 35 sx cement at 1020', displace with mud,

3rd plug pump 50 sx cement at 715',

4th plug pump 10 sx cement at 42 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:30 a.m. Day: 16 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pump 4 sx hulls and 25 sx cement at perfs, pressured up,

2nd plug pumped 35 sx cement at 1020', displaced with mud,

3rd plug pumped 50 sx cement at 715',

4th plug pumped 10 sx cement at 42 to -4'. Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 1022' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE 1-3-95
INV. NO. 41940
12-16

Signed Glenn R Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
12-21-94
DEC 21 1994