

1 020034

To:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation

Name &

Address P.O. Box 351

Liberal, KS 67901

Abandoned Oil Well _____ Gas Well _____ Input Well ☒ SWD Well ☒ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 19 Month: 9 Year: 1986

Plugging proposal received from Kirby Lillard

(company name) Sargents (phone) 316-624-7455

were: 5 1/2" at 4282 PBSD 4100 Perfs 4202-4211'

1st plug CIBP at 4100' with 20 sx cement using tubing.

2nd plug at casing cut with 30 sx cement

3rd plug at 1300-1100' with 40 sx cement

4th plug at 650-480' with 35 sx cement

5th plug at 50' with 10 sx cement

Plugging Proposal Received by Glenn Barlow

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part ☒ None _____

Operations Completed: Hour: 4 p.m. Day: 20 Month: 9 Year: 1986

ACTUAL PLUGGING REPORT 1st plug CIBP at 4100' with 20 sx cement on top of plug, Run with tubing.

2nd plug at 2015' with 30 sx cement

3rd plug at 1300-1100' with 40 sx cement

4th plug at 650-480' with 35 sx cement

5th plug at 50-0' with 10 sx cement

Heavy mud between all plugs.

Remarks: Recovered 2015' of 5 1/2" casing. Used common cement by Sargents.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-2-86

INV. NO. 15096

9-20

Signed

Glenn R. Barlow

(TECHNICIAN)