

1 020033

15-129-10441-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- completed 3/9/56  
C SE NE, SEC. 31, T 34 S, R 43 W/E  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67901

Lease Name Interstate Unit Well # 76  
County Morton 149.21  
Well Total Depth 4591 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1266

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10:30 a.m. Day: 23 Month: 9 Year: 1986

Plugging proposal received from Doug Blair

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4590' PBSD 4100' Perfs at 4203-4220'

- 1st plug CIBP with 20 sx cement using tubing
- 2nd plug at casing cut with 30 sx cement
- 3rd plug at 1300-1100' with 40 sx cement
- 4th plug at 650-480' with 35 sx cement
- 5th plug at 40-0' with 10 sx cement

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 23 Month: 9 Year: 1986

ACTUAL PLUGGING REPORT 1st plug CIBP at 4100' with 20 sx cement on top with tubing

- 2nd plug at 2200' with 30 sx cement,
- 3rd plug at 1300-1100' with 40 sx cement
- 4th plug at 650-480' with 35 sx cement
- 5th plug at 40-0' with 10 sx cement

Heavy mud spotted between all plugs.

10-2-86  
OCT 2 1986

Remarks: Recovered 2200' of 5 1/2" casing. Used common cement by Sargents.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If desired, observe this plugging.)

DATE 10-2-86

Signed Glenn R Barlow  
(TECHNICIAN)

INV. NO. 15095

9-23